

2

2:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Culvert								
col	9	1.3	1.3	0.45	6.84			
p.beam	9	0.2	0.2	4.65	1.67			
	3	6.8	0.2	0.3	1.22			
	2	5.8	0.2	0.3	0.70			
	1	2	0.2	0.2	0.08			
l/s beam	6	6.8	0.2	0.2	1.63			
	4	5.8	0.2	0.2	0.93			
	2	2	0.2	0.2	0.16			
chhajja	4	1.6	0.45	0.08	0.23			
slab	1	7.4	6.4	0.12	5.68			
					19.15	4163	cum	79730
5 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
Cold twisted bar / Hot rolled deformed steel	100	19.15			1915	53.5	kg	102453
6 Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
Foundations, footings, base of columns and plinth beam in any shape and size.	9	5.2		0.5	23.4			
	9	0.8		1.35	9.72			
c/l length	2	23		0.3	13.8			
					46.92	139	sqm	6522
Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
slab	1	7	3.8		26.6			
	2	3.4	2		13.6			
	9	0.8		3.3	23.76			
l/s beam	12	6.8		0.3	24.48			
	8	5.8		0.3	13.92			
	4	2		0.3	2.4			
chhajja	4	1.6	0.45		2.88			
					107.64	235	sqm	25295

