

OFFICE OF THE MUNICIPAL CORPORATION DURG

Estimate for Ward 28 C.C. Road construction from Kashbiya Band party to Hanuman Mandir.

1.6.09


Sl. No.	Name of Items	N	L	B	H	Qty	Rate	Amount	
(A)									
1.	Surface dressing of the ground including --- 50.0m lead.	1	100.0	8.60	-	860.0			
		1	115.0	7.60	-	874.0			
		1	45.0	4.80	-	216.0			
2.	Providing & laying nominal mix C.C. with 40mm CSA --- work. 1:4:8.	1	15.0	7.30	-	109.50			
						2059.50m ²	4.15/m ²	8547.0	
		1	230.0	3.0	0.10	69.0m ³	2057.0/m ³	141579.0	
3.	Providing & laying nominal mix C.C. with 20mm CSA --- form work. 1:1 1/2:3	1	100.0	8.60	0.10	86.0			
		1	115.0	7.60	0.10	87.40			
		1	45.0	4.80	0.10	21.60			
		1	15.0	7.30	0.10	10.95			
						205.95m ³	3240.95/m ³	66744.0	
								817540.0	
(B)									
1.	Application of Trininix machine method for C.C. pavement --- complete	1	100.0	8.60	-	860.0			
		1	115.0	7.60	-	874.0			
		1	45.0	4.80	-	216.0			
		1	15.0	7.30	-	109.50			
						2059.50m ²	76.0/m ²	156522.0	
Total (A+B) =							974062.0		
or say Rs.							974000.00		

Technical Sanctions is here by
 Accorded by G. P. A. G. W. H.
 in words अनुमोदित है

vide estt. No. /TS.1
 ..201.. Date... 11/7/16


 Exe. Engr
 Municipal Corporation, Durg

Ray
 Asstt Engr.
 Municipal Corporation, Durg


 Sub Engr
 Municipal Corporation, Durg