

2

Municipal Corporation Durg

**Estimate for Installation of Water Cooler with filter and platform at ward no 07,
Mathali Sharan Gupta Library under Parshad nidhi 2016-17**

The Estimate is Prepared as per S.O.R. of P.W.D. with effect from 01-01-2015 Raipur

S.O.R. Item

S.No.	Particulars	No.	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providinf and fixing M.S. grill of approved pattern made of square bars welded to steel frames.....coat of red oxide zinc chromate primer	1	110.00	1	1	110.00			
						110.00	Kg	67.50	7425.00
2	Providing and laying Nominal Mix mixed C.C.with usung concrete mixture with 20 mm graded metal in 1:1.5:3 C.C.	1	4.50	1.00	1.00	4.50			
						4.50	CuM	4073.0	18328.5
3	Providing and laying vitrified floor tiles of size 600x600mm with water absorption less than 0.5%.....including grouting the joints with cement and matching pigments etc. complete	1	30.00	1.00	1.00	30.00			
						30.00	Sq.M	710.00	21300.0
Total -									47053.5

20

Non S.O.R. Item									
ISI Mark Water Cooler 120 liter capacity (ISI Mark Water Cooler SS 60/120) with aquagard									
	1	1.00	1.00	1	1.00	No	52000.00	52000.00	
								52000.00	
S.O.R. Item									
Non S.O.R. Item									
								G Total	99053.5
								Say Rs	1.0 Lacs

Executive Engg.
Nagar Palik Nigam Durg

Recy

Asst. Engg.
Nagar Palik Nigam Durg

Sub

Sub Engg.
Nagar Palik Nigam Durg