

Municipal Corporation, Durg

N.I.T.

Estimate:- For 500 KVA,33/440V, Power Transformers No-01 Repair at 24 mld Filter plant, Durg

S.No.	Details of Item	Qty	Amount
1	Repairing of coil HV/LV	1 Job	
2	Cleaning, washing of dust and dirt from tank, cooling tubes & radiators		
3	change of power oil with filtration		
4	Replacement of silica gel breather with silica gel of 1kg capacity of good quality acrylic materials		
5	Replacement and repair of dia type thermometer and repair of magnetic type oil level gauge		
6	Sundry item, washer, nut-bolt, insulation material, minor repair of tank, radiator welding if required etc.		
7	H.T. Jointer kit & Oil gasket		
8	H.T. Oil seal bolt type complete		
9	H.T. Oil seal plain type		
10	L.T. Oil seal bolt type complete		
11	L.T. Oil seal plain type		
12	Cable legs, terminal nut-bolt & other necessary parts etc.		
13	Dismantling of transformer at Sub-Station. Durg at 24 mld intake, loading-unloading and transporting, core dismantling, core assembling, fitting, insulating of coil and lamination of core complete labour charges		
		Total	

Executive Engineer
Municipal Corporation, Durg

Contractor Name & Address

.....
.....

Witness Signature

1.
2.