


OFFICE OF THE MUNICIPAL CORPORATION DURG


Detailed Estimate


Name of work: Detailed estimate for Installation of water cooler with Filter and platform at ward no 24, Amdi mandir ward, under parshad nidhi 2014-15

As per PWD sor with effect from 01-01-2015 Raipur

S.No	Particulars	No.	Length	Width	Hight	Qty	Unit	Rate	Amount
1	Providing and fixing M.S. grill of approved pattern..... Coat of red oxide zinc chromate primer	1	110	1	1	110	kg	67.50	7425.00
2	Providing and laying nominal mix cc 1:1.5:3 with using concrete mixture with 20 mm graded metal.....	1	4.50	1	1	4.50	Cum.	4073.00	18328.50
3	Providing and laying vitrified floor tiles of size 600x600mm with water absorption..... etc complete	1	35.00	1	1	35.00	Sqm	710.00	24850.00
								Rs	50603.5
NON SOR ITEMS									
1	Usha waterCooler 120 liter Capacity (Usha water cooler SS60120)@ cost Rs 38900/-with Eureka Forbes Aquaguard Hi- flo , Direct Flow type or as required@ cost 10990/-	1	1	1	1	1	Compt. Job	50000.00	50000.00
								Total Rs	100603.5
								Say Rs	1.0 Lacs


Executive Engineer
Municipal Corporation Durg


Asstt. Engineer
Municipal Corporation Durg


Sub Engineer
Municipal Corporation Durg