

**Office of the Municipal Corporation, Durg**

**NIT**

**Name of work - Horticulture Work at Rajendra Park, Durg**

as per S.O.R. of P.W.D. With Effect From 01-01-2015

S.No.	Particulars	Qty	Unit
1	Trenching in ordinary soil upto a depth of 60cm including removal and stacking of serviceable materials and then disposing of by spreading and neatly leveling with in a lead of 50m and making up the trenched area to	1800	CuM
2	Extra rate for lead for every 50m lead or part thereof and upto 150 m beyond 50 m free lead and 1.5 m free lift by manual means only. For Soils	900	CuM
3	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be	1560	CuM
4	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km	260	CuM
5	Mixing earth and sludge or manure in proportion specified or	1820	CuM
6	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid	1820	CuM
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each	312	CuM
8	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately). In rows 5 cm apart in either direction	5200	SqM
9	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc Furn like Arica, China etc (3 year old) Hibiscus (Flower)/ Rose	4000 500 2000	Nos Nos Nos
10	Carriage by mechanical transport upto 5 km lead Earth	1800	CuM
11	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each	800	CuM



**Executive Engg.  
Municipal Corporation Durg.**